

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>38W</u>	<u>G-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REMONUMENTATION  
 OCT 30 1997  
 COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on August 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

(G-5) Corner of Sections 9, 10, 15 & 16, T50N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester Higgins, D.S., set post.  
 10" Spruce S 47° W 26 links  
 9" Balsam N 28° E 22 links

Stream crossings:  
 stream 3, SW, South 0.4 chains (26.4')  
 stream 3, SW, East 0.3 chains (19.8')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or B.T.s. Corner now falls in recently bulldozed logging road. The stream called for in original notes still exists but is now dry. I recreated the corner position at the intersection of the extension of centerline of county road to the East and the extension of old fence line to the South. This position works very well with original stream calls East and South and with distances to corners North and East. Distance to SW corner of Section 9 is 111 feet longer than GLO. This is, however, consistent with distances measured across Sections 4, 9, and 16. I believe this to be the result of either error or fraudulent work in the original survey. I believe this recreated position best represents the position of the original corner and have monumented it as such.

PEER GROUP APPROVED

Earl W. Applbaum  
 COUNTY REPRESENTATIVE 8-13-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped: COUNTY REMONUMENTATION; S.9, S. 10, S. 15, S. 16; T.50N, R.38W; 1997; P.S. 37273. Corner falls 6 feet North of centerline of logging road and 14 feet South of an East-West fence.

3" Hard Maple	N 62° W	20.22'
10" W. Birch	N 05° E	26.27'
5" W. Birch	S 61° E	38.69'
5" Cedar	S 29° W	54.90'
Steel Sign Post	West	0.83' (to face)
S 1/4 Cor. Sec. 10	S 89° 42' 19" E	2617.97'
W 1/4 Cor. Sec. 10	N 00° 40' 41" E	2654.87'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich Date 08/13/97

Surveyor's Michigan License No. 37273

