

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>38W</u>	<u>H-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on October 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(H-1) N 1/4 Corner of Section 3, T 50N, R 38W, on the 5th Correction Line

A. Description of original monument and accessories and/or subsequent restoration:  
 This corner was not set in the Original Survey.

In 1847, Sylvester W. Higgins, set Closing Corners on the 5th Correction line to the East and West of this corner.

Undated - Old Mining map of Algoma and Lake Mines; shows this corner midway between Closing Corners and on line between the South 1/4 corner and SE corner of Section 31, T 51N, R 37W. Distances to Standard Corners:  
 S 1/4 Cor. Section 31, T51N, R37W N 89° 38' W 1748.9'  
 SE Cor. Section 31, T51N, R37W S 89° 38' E 908.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no corner in place. I re-established the 1/4 corner midway between Closing Corners to East and West and on line between Standard Corners.

A fence intersection falls 35 feet West and 4 feet South of this position but was not accepted.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED  
*Carl W. Applekamp*  
 COUNTY REPRESENTATIVE  
 10-08-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; C.C.; 1/4; S. 3; T.50N, R.38W; 1997; P.S. 37273.

Witnesses:

5" Hard Maple	N 68° E	4.07'
19" Hard Maple	S 62° E	24.22'
6" Hard Maple	S 38° W	2.20'
10" Hard Maple	N 11° W	21.18'
S 1/4 Cor. Section 31, T51N, R37W	N 89° 43' 05" W	1749.34'
SE Cor. Section 31, T51N, R37W	S 89° 43' 05" E	905.50'



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joe C. Domitrovich  
 Surveyor's Michigan License No. 37273

Date 10/10/97