

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 50NR 38W H-3

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REMONUMENTATION

OCT 30 1997

COMMISSION

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on August 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(H-3) 1/4 Corner Common to Sections 3 & 10, T50N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester Higgins, D.S., set post.  
 8" Ironwood S 70° E 50 links  
 8" Sugar N 10° E 7 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. I found an old 1 3/4" pipe 3 feet above ground on the extension of a fence to the West. If falls 18 feet East of a fence to the South. The pipe is N 34° E 2.3 feet from the theoretical single prorated position. I accepted the pipe as the 1/4 Corner and drove it down to 12" above ground.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" rebar driven into a 1 3/4" iron pipe and capped with a 3" diameter aluminum cap stamped: COUNTY REMONUMENTATION; 1/4; S. 3, S. 10; T.50N, R.38W; 1997; P.S. 37273.

Witnesses:

6" Soft Maple	N 37° E	22.79'
11" Maple	S 57° E	32.23'
5" Hard Maple	S 40° W	16.80'
7" Ash	West	29.09'
Steel Sign Post	North	0.93' (to face)
NW Cor. Sec. 10	N 89° 40' 56" W	2617.36'
NE Cor. Sec. 10	S 89° 35' 54" E	2614.78'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich

Surveyor's Michigan License No. 37273

Date 8/13/97

PEER GROUP APPROVED  
Paul W. Applekamp  
 COUNTY REMONUMENTATION  
 8-13-97

