

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In: _____	Corner Code # _____
1. Public Land Survey	T <u>50N</u> R <u>38W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on October 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

(I-1) Closing Corner on the 5th Correction Line, Sections 2 & 3, T 50N, R 38W

A. Description of original monument and accessories and/or subsequent restoration:

- 1847 - Sylvester W. Higgins intersected North Boundary 13 chains 69links West of 1/4 post in Section 32, T 51N, R 37W, and set post.  
 8" Sugar S 65° W 13 links 10" Lynn S 50° E 11 links
- Undated - Old mining map of Algoma and Lake Mines shows this corner but does not indicate what it is. Bearings and distances to corners East-West and South are also noted. (Distances noted in 'B' below.)
- 1935 - Leo Chantelois, Field Assistant for U.S. Forest Service, noted on Form 874-9, found scribing on a 19" hard maple stump. He placed a metal location poster on a 13" diameter hemlock 29 links to the West. He also noted the corner fell at the NW corner of an open field.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the rotted remains of the 8" Sugar bearing tree. It is now a 20+" rotted mass. At record bearing and distance from the B.T., I found a 1 1/4" iron pipe at a fence intersection, fences running East, West, and South. I also found the remains of the 1935 hemlock but could not find the location poster. This corner works well with GLO and old mining map distances to other corners on the correction line and to the South.

East 1/4 Cor. Section 3	S 00° 27' 14" E	1937.29' (m)	1934.46' (GLO)	1936.50' (old map)
SW Cor. Section 32, T51N, R37W	S 89° 45' 31" W	1741.43' (m)	1736.46' (GLO)	1741.8 (old map)
NW Cor. Section 3	N 89° 56' 27" W	5293.81" (m)	5277.36' (GLO)	5299.7' (old map)

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 48" aluminum rod driven inside the 1 1/4" iron pipe, capped with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; C.C.; S. 2, S. 3; T.50N, R.38W; 1997; P.S. 37273.

Witnesses:

5" Hard Maple	S 78° E	22.56'	
8" Twin Hard Maple	S 23° W	25.29'	
10" Hemlock	S 77° W	36.97'	
28" Hemlock	N 23° W	40.48'	
Steel Sign Post	North	0.60'	(to face)

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY REPRESENTATIVE  
 10-08-97



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J.C. Domitrovich Date 10/8/97  
 Surveyor's Michigan License No. 37273