

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>50NR 38W</u>	<u>J-1</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

**SURVEY & REMONUMENTATION**

**APR 07 1998**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on November 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

(J-1) North 1/4 Corner of Section 2, T 50N, R 38W

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set in the original GLO survey. Closing Corners to the East and West were set by Sylvester W. Higgins in July 1847. The corners on the South side of T 51N, R 37W, defining the correction line, were set by Austin Burt, in 1845.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 1/2" iron pipe 3 feet above ground. This pipe is 6.8 feet South and 19.1 feet East of a prorated position and does not match the intended position for the 1/4 corner.

I created a position for the 1/4 Corner midway between Closing Corners and on the correction line between the South 1/4 Corner and the Southeast Corner of Section 32, T51N, R37W, and monumented it as the North 1/4 Corner of Section 2. It falls 11 feet South of Centerline of Post Office Road to the West and 10 feet West of centerline of Post Office Road to the South.

**DEER GROUP APPROVED**

*Paul W. Appleton*  
 COUNTY REMONUMENTATION 11-11-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T.50N, R.38W; C.C.; 1/4; S. 2; 1997; P.S. 37273.

8" Soft Maple	S 38° W	77.66'	
Steel Sign Post	North	0.82'	(to face)
6" Hard Maple	N 17° W	55.48'	
8" Hard Maple	N 41° E	17.68'	
1 1/2" Iron Pipe	S 71° E	20.10'	
S 1/4 Cor. Section 32 (T51N, R37W)	N 89° 40' 01" E	1010.56'	
SE Cor. Section 32 (T51N, R37W)	S 89° 40' 01" W	1647.29'	

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich  
 Surveyor's Michigan License No. 37273

Date 11/10/97

