

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 38W	J-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY &
 REMONUMENTATION

OCT 30 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on August 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3									●			
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

(J-3) 1/4 Common to Sections 2 & 11, T50N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester Higgins, D.S., set 1/4 post.
 14" Sugar N 32° W 10 links
 8" Y. Birch S 52° E 31 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories have been destroyed by farming and road construction. The corner now falls in a North-South gravel road on the extension of fences to the East and West. At the intersection of centerline and fences, I dug down 18" and found a 3/4" iron pin and remains of a wooden post. This iron pin falls N 27° W 8.9 feet from the theoretical single prorated position. It is, however, the best remaining evidence of the original 1/4 corner, and it is consistent with over 60 years of occupation and land use.

I, therefore, accepted the iron pin as the 1/4 corner.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Earl W. Applbaum
 COUNTY REPRESENTATIVE 8-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" rebar driven over the 3/4" iron pin, capped with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; 1/4; S. 2, S. 11; T.50N, R.38W; 1997; P.S. 37273. I also established a reference monument (R.M.) to the West, a 2" x 30" aluminum pipe with a 3" dia. aluminum cap stamped to indicate that the corner is East 28.04'.

Witnesses:

6" Elm	N 40° W	83.41'
7" Soft Maple	S 84° E	52.22'
Power Pole	S 15° W	123.58'
R.M.	S 86° 40' 29" W	28.04'
NE Cor. Sec. 11	S 89° 55' 59" E	2656.01'
NW Cor. Sec. 11	S 89° 43' 27" W	2647.97'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 8/13/97

