

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>39W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on November 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

(C-1) Closing Corner Common to Sections 6 & 5, T50N, R39W

A. Description of original monument and accessories and/or subsequent restoration:

- 1847 - Sylvester W. Higgins intersected the correction line on North Boundary 7 chains 24 links (477.84 feet) West of the 1/4 corner of Section 35, T51N, R39W, and set post.  
 6" Sugar S10° W 20 links  
 8" Ironwood S 42° E 41 links
- 1947 - Michigan State Highway Department, for U.S. Highway 45 highway plans, shows this corner as being a 1" gas pipe and gives 3 bearing trees.  
 5" Maple N 30° W 2.35'  
 2" Maple S 52° W 23.13'  
 10" Hemlock S 30° E 7.38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories were not recovered. Corner now falls in an old farm field, and by all indications, the field was in existence at the time of the Highway Department Survey. (The 1" pipe and bearing trees, noted above, match the corner recovered at the SW Corner of Section 35, T51N, R39W.)

I re-established the corner at the proportionate distance from the South 1/4 Corner of Section 35, T51N, R39W and on line between the South 1/4 Corner and SW Corner of Section 35, T51N, R39W. This position works well with other corners in the area.

PEER GROUP APPROVED

*Carl W. Applbaum*  
 COUNTY REGISTER 12-01-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T.50N, R.39W, S. 6, S. 5; C.C.; 1997; P.S. 37273.

Witnesses:

18" Hard Maple	S 80° E	133.65'
24" Basswood	S 30° E	199.03'
Steel Sign Post	South	1.30' (to face)
Steel Sign Post	West	1.56' (to face)
SW Cor. Section 35, T51N, R39W	S 89° 50' 53" W	2154.64'
S 1/4 Cor. Section 35, T51N, R39W	N 89° 50' 53" E	476.18'



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich  
 Surveyor's Michigan License No. 37273

Date 11/30/97