

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/ 15 JEM Fee: 9.00
12/28/95
12:09
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------------------|----------------|
| Ontonagon (County) | Located In: | Corner Code #: |
| 1. Public Land Survey | T 50N R 39W | E3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | ⊕ | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Dennis R. Destrampe, in a field survey on October 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post
Lynn 14 S25E 14
Y Birch 20 N40W 30

Corner shown on survey of section by Robert A. Mick, R.L.S. 16936, dated October 3, 1983, recorded in Survey Book 1, Page 68, Ontonagon County Register's Office. Corner recorded March 23, 1984, L.C.R.C. Liber 2, Page 150, by Robert A. Mick.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found of original corner or accessories. Found a 1/2" capped pin as recorded, bearing trees gone due to clear cut logging, found stumps that fit bearing tree locations. Traversed perimeter of section, agreed within reason with Mick survey dimensions. Accepted corner as found. Research data on file with the county representative.

PEER GROUP APPROVED

Earl W. Applbaum 12-14-95
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" iron pin with a standard 2"x30" aluminum pipe monument with a 3 1/2" aluminum cap 0.5' above ground. Cap stamped:

COUNTY REMONUMENTATION

The following witnesses were established:

- 2" Sugar Maple S38°E 28.85' (Nail & tag "UPEA 18983")
- 8" Sugar Maple S57°W 46.24' (Nail & tag "UPEA 18983")
- 3" Ironwood S76°W 8.29' (Nail & tag "UPEA 18983")
- 4" Sugar Maple N28°W 65.11' (Nail & tag "UPEA 18983")
- 6' Steel Sign Post S49°W 0.61'

T50N R39W
S5 | S4
S8 | S9

All bearing trees blazed and scribed NBT

Signed by *Dennis R. Destrampe*
Surveyor's Michigan License No. 18983

Date 10/12/95

1995
PS 18983