

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM 12/28/95
 Ontonagon County 12:10
 LC 4/ 17 JEM Feet 9.00
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon (County)	Located In:	Corner Code --#
1. Public Land Survey	T 50N R 39W	E5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Dennis R. Destrampe, in a field survey on October 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post
 Sugar 20 N40E 11
 Lynn 6 S30W 22

Corner shown on survey of section by Robert A. Mick, R.L.S. 16936, dated October 3, 1983, recorded in Survey Book 1, Page 68, Ontonagon County Register's Office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found of original corner or accessories. Found metal monument and witnesses as described in Mick survey. Traversed perimeter of section, agreed within reason with Mick survey dimensions. Accepted corner as found. Research data on file with the county representative.



PEER GROUP APPROVED

Earl W. Applekamp 12-14-95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced metal monument with a standard 2"x30" aluminum pipe monument with a 3 1/2" aluminum cap 0.5' above ground. Cap stamped:

The following witnesses were established:

- E face 8" Fence Post N11°W 5.91' (Nail & tag "UPEA 18983")
- N face 6" Fence Post S85°E 13.87' (Nail & tag "UPEA 18983")
- W face 6" Sugar Maple S54°E 12.54' (Nail & tag "UPEA 18983")
- S face 7" White Ash N79°E 37.20' (Nail & tag "UPEA 18983")
- 6' Steel Sign Post S35°W 3.22'

COUNTY REMONUMENTATION

T50N R39W

S8	S9
S17	S16

All bearing trees blazed and scribed NBT

Signed by Dennis R. Destrampe
 Surveyor's Michigan License No. 18983

Date 10/12/95

1995
 PS 18983