

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T50N R 42W	C-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
 REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 7 & 8, T50N R42W.

I, Earl W. Applekamp, in a field survey on May 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, June 19, 1848. Set Hemlock Post.

ORIGINAL BEARING TREES:

12" Cedar S62°E 3.30 feet
 8" Sugar N88°W 22.44 feet

DEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTERED 6-9-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a 4" square Cedar Post lying on the ground. It was scribed S8 on one side and $\frac{1}{4}$ on another. One other side had evidence of scribing but was partially decayed. The fourth side was badly decayed. No record is available as to who set this. The 12" Cedar original bearing tree which has uprooted years ago, was lying in a position above ground with a sound shell. It was 19" in diameter at the blaze which was an elongated hole. The measure mark was also an elongated hole. The 4" squared Cedar Post was at the called distance from the Cedar. I accepted this position and monumented the corner.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T50N R42W, S7, S8, $\frac{1}{4}$, 1999, P.S. 17610. I established three bearing trees and a reference object.

Nail in 9" Hemlock S60°W 32.40' - Nail in 11" hemlock S27°E 24.97'
 Nail in 6" S. Maple Due North 6.69' - 6' Steel Sign Post Due West 0.90'



Signed by *Earl W. Applekamp*

Date May 25, 1999

Surveyor's Michigan License No. 17610