

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
(County)

Located in:

Corner Code #

- | | | | | | | |
|------------------------------------|---|----|---|----|---|-----|
| 1. Public Land Survey | T | 50 | R | 42 | | E-1 |
| | T | | R | | | |
| | T | | R | | | |
| | T | | R | | | |
| 2. Property Controlling in Section | S | | T | | R | |
| | S | | T | | R | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | |
| | S | | T | | R | |

Recorded December 5 1994
at 2:05 o'clock P. M. in
Liber 3 page 226
Julia M. ...
Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 4 & 5, T50N R42W

Earl W. Applekamp in a field survey on November 05, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt, Deputy Surveyor, June 1848.
Set Wood Post.

- | | | | | |
|-------------|-----|-------|----------|----------|
| Sugar Maple | 12" | S68°W | 36 Links | (23.76') |
| Hemlock | 28" | S62°E | 22 Links | (14.52') |

ONTONAGON COUNTY

PEER APPROVED

Earl W. Applekamp
Dist. Co. Rep
11-30-94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a 1½" well point marking the corner. A 5" squared cedar post was laying on the ground. This well point had been at the corner position since 1948 or before and was used when the Copper Range Mine was being developed. In 1961 it was tied to the Copper Range Co-ordinate System and has a value of N34936.38 and E29986.72. I replaced the well point with permanent monument described below.

Research on file with County Remonumentation Program Representative.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2¼"x30" aluminum pipe with a 3¼" cap stamped to read: County Remonumentation, S4, S5, T50N R42W, 1994 P.S. 17610. The following trees and objects were used to tie in the corner.

- | | | |
|----------------------|-------|--------|
| 14" Hemlock | N17°W | 39.90' |
| 15" Hemlock | S50°E | 13.95' |
| 9" Maple | N67°E | 36.80' |
| Steel Sign Post West | | 1.05' |



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date November 28, 1994