

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T50N R 42W	E-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &
REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 4 & 5, T50N R42W.

I, Earl W. Applekamp, in a field survey on April 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	●	4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	19			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, June 15, 1848. Set Yellow Birch Post.

ORIGINAL BEARING TREES:

12" Hemlock	S12°E	10.56 feet
24" Hemlock	N25°W	10.56 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTERED SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position falls in a cut section for Michigan Highway M-64. Corner was re-established by single proportionate measure and on line between opposite section corners, North & South.

5-11-99

Research on file with the Ontonagon County Remonumentation Program Representative



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T50N R42W, S4, S5, 1/4, 1999, P.S. 17610. I established the following bearing objects.

- Nail in 9" W. Ash, S88°-21'-33"W, 140.29' - Nail in P. Pole, S21°-44'-13"E, 5.17'
- Center-line Hwy M-64 S84°W 52.89' - Nail in 9" Hemlock N42°-23'-32"E 51.65'
- 6' Steel Sign Post Due East 0.60' - Copper Range Coordinates N32640.13 - E29992.90

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date April 21, 1999