

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: ONTONAGON (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SURVEY & REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

1/4 Corner common to Sections 8 & 9, T50N R42W.

I, Earl W. Applekamp, in a field survey on April 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-12. A dot is marked at the intersection of column E and row 4.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, June 15, 1848. Set Hemlock Post.

ORIGINAL BEARING TREES:

36" Hemlock S35°E 17.16 feet
18" Hemlock N50°W 7.92 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found. Area has been extensively logged. Corner was re-established by single proportionate measure and on line with opposite section corners North and South.

Research on file with the Ontonagon County Remonumentation Program Representative

PEER GROUP APPROVED
Earl W Applekamp
COUNTY REGISTERED 5-11-99



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T50N R42W, S8, S9, 1/4, 1999, P.S. 17610. I established the following bearing objects:

Nail in 15" Hemlock N15°W 41.00' - Nail in 9" Hemlock S36°E 20.02'
Nail in 16" Hemlock N56°E 50.98' - 6' Steel Sign Post Due West 0.82'
Copper Range Coordinates N27366.55 E29993.56

Signed by Earl W Applekamp
Surveyor's Michigan License No. 17610

Date April 23, 1999