

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon Located In: Corner Code #
 (County)

1. Public Land Survey T 50N R 42W E-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDATION
 OCT 3 0 1997
 COMMISSION
 Register of Deeds Stamp & File Number

Section Corner 28, 29, 32 & 33; T.50 N., R.42 W.

I, Richard L. Drahn in a field survey on May 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established By Austin Burt on June 14, 1848. Original B.T.s --- 10" Fir S.60 E. 30 links (19.80') --- Sugar Maple 20" N.15 W. 5 links (3.30')

Donald Lappala (12585) restored this corner by analysis of his retracement survey and from natural features on 9/2/65. He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following new B.T.s --- 11" (16") Hemlock N.35 W. 25.9' (25.87') --- 6" (12") White Ash N.10 E.37.1' (36.87') --- 12" (13") Sugar Maple S.40 W. (S.39 W. 28.6' (28.69") ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner. Corner recorded in USFS Liber Page V-9 on 6/3/68 of Ontonagon County Records.

Corner position found marked by the monument as described and the B.T.s as indicated in parentheses above. No evidence of GLO B.T.s recovered.

Research form on file with Ontonagon County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following:

6" Steel sign rail N.73 E. 1.96'

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 5-12-97



Signed by Richard L. Drahn Date May 9, 1997

Surveyor's Michigan License No. 21564