

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T50N R 42W	G-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner common to 3 & 4, T50N R42W on Fifth Correction Line.

I, Earl W. Applekamp, in a field survey on May 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, June 15, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

16" Sugar Maple	S41°E	30.36 feet
16" Yellow Birch	S50°W	25.08 feet

FEEL GROUP APPROVED  
Earl W. Applekamp  
 COUNTY REGISTRAR  
 6-17-98



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. In mid 1940 Copper Range Company Cruisers marked the corner. Subsequently it was tied to the Copper Range Co. coordinate system. In early 1960 this area was disturbed for construction of a Tailings Dam immediately North of the Fifth Correction Line. The corner was re-established using the Copper Range Company coordinates. This position is in conformance with the original field note calls. The corner was set at Copper Range coordinates, N34918.71 & E35246.07 feet. This position is in a pond so two Witness Monuments were set.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Because the corner position falls in a pond, I set two Witness Corners on the Section Line West of the true corner. These monuments are 2 1/2" X 30" split base aluminum pipe with a 3" stamped cap. The first Witness Monument is stamped: County Remonumentation, T50N R42W, W.M., S3, S4, S89°-43'-50"E, 182.40', 1998, P.S. 17610. The second Witness Monument was stamped: County Remonumentation, T50N R42W, W.M., S3, S4, N89°-43'-50"E, 334.57', 1998, P.S. 17610.

<u>BEARING TREES FOR FIRST WITNESS MONUMENT</u>	-	<u>BEARING TREES FOR SECOND WITNESS MONUMENT</u>
Nail in 11" Maple N52°E 11.63'	-	Nail in 9" W. Ash N83°E 39.90'
Nail in 10" Maple S10°W 19.23'	-	Nail in 11" Hemlock S10°W 29.77'
Nail in 8" Maple S84°W 12.80'	-	Nail in 4" Maple N69°W 44.54'

Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date June 1, 1998