

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T50N R42W	G-3
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

**SURVEY &
REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 3, 4, 9 & 10, T50N R42W.

Earl W. Applekamp, in a field survey on Dec. 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3						●						
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt, U.S. Deputy Surveyor, June 15, 1848. Set Yellow Birch Post.

ORIGINAL BEARING TREES:

16" W. Ash	S74°E	24.42 feet
12" Hemlock	N39°W	21.78 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 5-11-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence was found. There is an abandoned Railroad grade running East & West at this location. In the mid 1950's I was told by Victor Arcand, RLS, now deceased, that this RR grade (named Boyds Grade) was on the section line. Mr. Arcand had worked for Copper Range in the area from the late 1940's through 1966. The Corner one mile East of this corner position is destroyed by a Tailings Dam. I established the departure of the corner by using a stream call East and the Section Corner 1 mile West and accepted the Railroad Grade for the latitude.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 At the corner position I set a 2 1/2"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T50N R42W, S3, S4, S9, S10, 1998, P.S. 17610. I established three bearing trees and a reference object.

Nail in W. Ash	S04°E	31.32'	-	Nail in 9" Basswood	N31°E	32.78'
Nail in 9" Ash	N65°W	26.87'	-	6' Steel Sign Post	West	0.91'
Copper Range Coordinates		N30011.57'		E35246.73'		



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date April 20, 1999