

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>ONTONAGON</u><br>(County)          | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>50N</u> R <u>42W</u> | <u>G-4</u>    |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |

**SURVEY &  
 REMONUMENTATION**

**MAR 23 2000**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Section 9 & 10, T50N R42W.

I, Earl W. Applekamp, in a field survey on Dec. 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  | ● | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, June 15, 1848. Set Ironwood Post.

ORIGINAL BEARING TREES:

18" Lynn S62°E 23.76 feet  
 14" Lynn N47°W 19.14 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original or other evidence was found. Corner was re-established by single proportionate measure between opposite section corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVAL  
Earl W. Applekamp  
 COUNTY SURVEYOR  
 5-11-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T50N R42W, S9, S10, 1/4, 1998, P.S. 17610. I established three bearing trees and a reference object.

Nail in 9" H. Maple N69°W 31.47' - Nail in 7" H. Maple S88°E 25.60'  
 Nail in 6" H. Maple N22°E 25.59' - 6' Steel Sign Post Due South 0.91'  
 Copper Range Company Coordinates N27381.47' E35247.08'



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date April 19, 1999