

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50NR 42W	G-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property In Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 9, 10, 15 & 16, T50N R42W.

I, Earl W. Applekamp, in a field survey on Dec. 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, June 18, 1848. Set Hemlock Post.

ORIGINAL BEARING TREES:

12" Sugar Maple	S42°E	14.52 feet
28" Hemlock	N48°W	18.48 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY SURVEYOR
 5-11-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the corner position I found a 1" pipe with a 2" cap in the North ditch of the L.P. Walsh Road. This corner is identified on the construction drawings of the L.P. Walsh by Scott Engineering Co. dated July 29, 1962. This corner was not recorded. I accepted the corner position and monumented it as shown in C.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" pipe described in B. above with a 2 1/2" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T50N R42W, S9, S10, S15, S16, 1998, P.S. 17610. I established the following bearing objects:

Nail in P. Pole	S20°W	110.34'	- Center-line L.P. Walsh Road	South	41.76'
Nail in P. Pole	N01°E	70.54'	- 6' Steel Sign Post	North	0.55 feet
Nail in P. Pole	N47°E	42.97'	- Copper Range Co. Coordinates	N-24751.37	and E-35247.44



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date April 29, 1999