

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
 Ontonagon County
 LC 3/ 318 JEM Fee: 9.00
 09/25/95 14:41
 Page 1 of 1

For corners in

Ontonagon (County)	Located In:	Corner Code ##
1. Public Land Survey	T 50 N R 42 W.	H-13 ✓
	T 49 N R 42 W.	H-13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 3 & 34, T.49-50 N., R.42 W.

I, Richard L. Drahn, in a field survey on August 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by William Burt on August 18, 1847. Original B.T.s --- Sugar 12" N.75 E., 10 links (6.60') --- Sugar 12" N.38 W., 24 links (15.84').
 Corner restored by Richard L. Drahn, R.L.S. 21564 on 9/26/78 from the stump holes and wood fragments of the original B.T.s and from line tree remains, natural feature ties and distance to corners east and west. 1978 new B.T.s --- 6" (7") Sugar Maple s.60 W. (S.64 W.) 13.9' (13.87') --- 9" (11") Sugar Maple N.03 E. (N.05 E.) 20.4' (20.34') --- 9" (13") Sugar Maple S.60 E. (S.57 E.) 23.5' (23.50') --- 7' Metal sign Post N.24 W. (N.20 W.) 3.3' (3.25')

Recorded in Liber 1, Page 164 on April 25, 1979 in Ontonagon County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Recovered 2" by 5' long galvanized iron pipe with stamped brass cap set on 9/26/78 by Richard L. Drahn. Data in parenthesis above are size, bearings and distances found on 8/21/98. No fragments of Sugar maple wood found in GLO B.T. stump holes.

Act 74 research form on file with Ontonagon County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree established:

8" Sugar Maple N.58 W. 7.94'

PEER GROUP APPROVED

Earl Anshaus 9-20-95
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date September 10, 1995

Surveyor's Michigan License No. 21564