

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHN
Ontonagon County
LC 3/320 JEM Fee: 9.00
Page 1 of 1

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>42</u> W.	<u>I-13</u> ✓
	T <u>49N</u> R <u>42</u> W.	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Sec. Cor. 2, 3, 34 & 35; T.49-50 N., R.42 W.

I, Richard L. Drahn in a field survey on August 21 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on August 18, 1847. Original B.T.s --- Sugar 14" N.41 E., 30 links (19.80') --- Y. Birch 12" N.29 W., 18 links (11.88') --- Y. Birch 30" S.11 W. 28 links (18.48') --- Sugar 24" 56 links (36.96') S.67½ E.

Corner restored by Richard L. Drahn, RLS 21564 on 8/22/77 from the remains of the four original bearing trees and from natural feature ties and line trees south and west. He set a 2' by 5' galvanized iron pipe monument with a 3" stamped brass cap and the following new B.T.s --- 8" Sugar Maple N.37 E., 11.0' (B.T. now dead) --- 6" Sugar Maple S.56 E., 39.8' (now dead and down)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7" (9") Sugar Maple S.89 W. (N.89 W.) 24.5' (24.50') --- 7' Metal sign post S.05 E. (South) 3.0' (2.75'). Recorded in Liber 1, Page 166 on 4/25/79 in Ontonagon County.

Recovered monument as described. Bearing trees recovered as described in parentheses above. Fragments of wood and bark recovered from the first and third GLO bearing trees. Only stump holes remain of the other two.

Act 74 research form on file with Ontonagon County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees established;

- 10" Sugar Maple N.10 E. 20.27'
- 16" Sugar Maple S.28 W. 16.13'

PEER GROUP APPROVED
Paul Applekamp 9-20-95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date September 10, 1995
Surveyor's Michigan License No. 21564