

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>42W</u>	<u>K-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SURVEY &
 REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 11, 12, 13 & 14, T50N R42W.

I, Earl W. Applekamp, in a field survey on Dec. 07, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by Austin Burt, U.S. Deputy Surveyor, June 10, 1848. Set Ironwood Post. ORIGINAL BEARING TREES: Sugar 12", S54°E, 72 Links (47.52 Feet). Lynn 10", N50°W, (20.46 Feet). During construction of the L.P. Walsh Road, corner was restored. The drawings prepared by R.S. Scott Engineering Co. Inc., of Alpena, Michigan, dated July 29, 1967, identify the corner at Station 131+83.2 and 42 feet North of the centerline of the L.P. Walsh Road. This information was not recorded with the Register of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Based on the information above, I found a 3/4"x24" pipe with a 2" brass cap flush with the ground. I accepted this as being the only logical position for the corner. I replaced the 3/4" x24" pipe w/cap and set a monument described in "C" below.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" split base aluminum pipe with a 3" cap flush with the ground. Cap is stamped to read: County Remonumentation, T50N R42W, S11, S12, S13, S14, 1999, P.S. 17610. I established five bearing objects.

- Nail in N. side of P. Pole N77°W 150.50' - Centerline of L.P. Walsh Road, South 41.65'
- Nail in N. side of P. Pole N75°E 101.32' - 6' Steel Sign Post, North 0.53'
- Nail in 7" W. Ash S11°W 137.42'

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 12-20-99



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date December 10, 1999