

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
 Ontonagon County
 LC 3/312 JEM Feet 9.00
 Page 1 of 1
 09/25/95
 14:24

For corners in

<u>Ontonagon</u> (County)	Located in:	Corner Code ##
1. Public Land Survey	T 49N R 43 W.	D-1
	T 50N R 43 W.	D-13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner 5 & 32; T.49-50 N., R.43 W.

I, Richard L. Drahn, in a field survey on August 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on August 18, 1847. Original B.T. s --- Sugar 8" N.46 E. 18 links (11.88') --- Sugar 12" N.65 W. 24 links (15.84').

Corner restored by Richard L. Drahn, RLS 21564 on September 22, 1982 from the decayed remains of the NW B.T., a natural feature tie west and distance ties to recovered corners east and west. He set a 2" by 30" aluminum pipe with a stamped aluminum cap and the following new B.T.s: --- 5" (5") Red Maple N.25 E. (N.27 E.) 26.71' (26.78') --- 12" (12") Sugar Maple S.26 E. (S.27 E.) 29.98' (29.97') --- 18" White Pine (cut down) N.89 W. 28.91'. ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered monument as described and the bearing trees as described in parentheses above. A windthrown stump hole remains from the original NW B.T.

Corner recorded in Ontonagon County in Liber 2, Page 26 on 4/28/83.

Act 74 research form on file with Ontonagon County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- 27" White Pine S.64 W. 40.18' (B.T. by RLS 21564 on 5/10/88)
- 5" Sugar Maple S.65 E. 11.15'
- 6' Steel rail N.09 W. 1.8'

PEER GROUP APPROVED
Paul Applbaum 9-20-95
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 11, 1995

Surveyor's Michigan License No. 21564