

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County
LC 3/ 313 JEM Feet 9.00
09/25/95
14:26
Page 1 of 1

For corners in

<u>Ontonagon</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>49N</u> R <u>43</u> W.	<u>E-1</u>	
	T <u>50N</u> R <u>43</u> W.	<u>E-13</u> ✓	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 4, 5, 32 & 33: T.49-50 N., R.43 W.

I, Richard L. Drahn, a field surveyor on August 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt in 1847. Original B.T.s --- White Pine 30" N.77 E. 22links (14.52') --- Aspen 10" N.14 W. 28 links (18.48') --- White Ash 10" S.45 W. 25 links (16.50') --- Maple 10" S.41 E. 54 links (35.64').

Corner restored by Donald D. Lappala, RLS 12585 on 8/6/68 from scribed remains of the White Pine and White Ash bearing trees. He set a 2" by 5" galvanized iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 6" Sugar Maple (dead and down) N.21 W. 11.9' --- 8" (10") Sugar Maple S.51 E. (S.55 E.) 14.7' (14.67') --- 6" (8") Sugar Maple S.18 W. (S.20 W.) 10.8' (10.87')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in USFS Liber, Page A-9 on 4/1/69.

Act 74 research form on file with Ontonagon County records.

Recovered monument as described and the bearing trees as described in parentheses above. A decayed W. Pine stump and fragments of W. Ash wood still remains from the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Bearing objects referenced:

13" Cedar N.15 W. 66.69' (B.T. by RLS 21564 on 5/10/88)

6' Steel rail N.72 E. 2.58'

PEER GROUP APPROVED

Earl Kopke 9-20-95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 11, 1995

Surveyor's Michigan License No. 21564