

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM  
Ontonagon County  
LC 3/314 JEM Fee: 9.00  
Page 1 of 1

For corners in

Ontonagon  
(County)

Located In:

Corner Code ##

- |                                    |                              |               |
|------------------------------------|------------------------------|---------------|
| 1. Public Land Survey              | T <u>49</u> N R <u>43</u> W. | <u>F-1</u>    |
|                                    | T <u>50</u> N R <u>43</u> W. | <u>F-13</u> ✓ |
|                                    | T _____ R _____              | _____         |
|                                    | T _____ R _____              | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____      | _____         |
|                                    | S _____ T _____ R _____      | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____      | _____         |
|                                    | S _____ T _____ R _____      | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 Corner 4 & 33; T.49-50 N., R.43 W.

I, Richard L. Drahn, in a field survey on August 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on August 18, 1847. Original B.T.s --- Cedar 4" N.73 E. 20 links (13.20') --- Maple 12" N.65 W. 28 links (18.48') ---

Corner restored by Richard L. Drahn, RLS 21564 on 9/22/82 from the original 19" Cedar B.T, alive and with GLO blazes and measuring notch and distance to a line tree east and distances east and west to recovered section corners. He set a 2" by 30" aluminum monument with a 3 1/4" stamped aluminum cap and the following new B.T.s: --- 10" (13") Hemlock N.66 E. (N.62 E.) 23.89' (24.10') --- 12" (14") Hemlock S.66 E. (S.68 E.) 36.96' (36.95') --- 10" (11") Cedar S.24 W. (S.26 W.) 17.44' (17.43') 6' Steel rail S.03W. 1.25' (1.22') ---.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in Liber 2, Page 80 on 4/28/83.

Act 74 research form on file with Ontonagon County records.

Recovered monument as described and the bearing trees as noted in parentheses above. The original Cedar bearing tree is now 21" and still alive.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing Objects referenced:

6' Metal sign post S.03 W. 1.22'

6" Sugar Maple N.02 W. 14.52'

PEER GROUP APPROVED

*Earl Applebaugh 9-20-95*  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date September 11, 1995

Surveyor's Michigan License No. 21564