

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 3/315 JEM Fee: 9.00
 09/25/95
 14:32
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 43 W. T 50N R 43 W. T _____ R _____ T _____ R _____	G-1 G-13 ✓
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sec. Cor. 3, 4, 33 & 34; T.49-50 N., R.43 W.

I, Richard L. Drahn in a field survey on August 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on August 18, 1847. Original B.T.s --- Fir 10" N.32 E. 32 links (21.12') --- Aspen 10" N.10 W. 25 links (16.50') --- Elm 8" S.60 E. 35 links (23.10') --- Spruce 5" S.40 W. 10 links (6.60') ---.

Corner restored by Richard L. Drahn, RLS 21564 on 9/22/82 from the 19", live Elm B.T. still scribed and the decayed remains of two other B.T.s He set a 3/4" by 4' solid aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s: --- 5" (9") White Spruce S.89 W. (N.86 W.) 7.59' (7.59') --- 5" (8") White Spruce S.55 E. (S.52 E.) 11.57' (11.57') --- 10" Cedar S.24 W. (S.27 W.) 31.20' (31.21') --- 6' Metal sign post S.09 E. (S.05 E.) 2.1' (2.10') ---.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in Liber 2, Page 90 on 4/28/83.

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. The original Elm B,T, is now dead and down with scribing still visible on the stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

6" White Spruce N.14 E. 29.18'

PEER GROUP APPROVED

Carl Applekamp 9-20-95
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 11, 1995

Surveyor's Michigan License No. 21564