

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. 51 <sup>N.</sup> / <sub>S.</sub> , R. 37 <sup>E.</sup> / <sub>W.</sub>	L-3, L-4	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION _____	, T. 51 <sup>N.</sup> / <sub>S.</sub> , R. 37 <sup>E.</sup> / <sub>W.</sub>	10, 1	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> / <sub>S.</sub> , R. _____ <sup>E.</sup> / <sub>W.</sub>		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner L-3: Original monument and accessories not found. Found MSHD reference post S11°W 35.5'.
  - Corner 10: Not set on original survey nor subsequently apparently.
  - Corner 1: Not set on original survey nor subsequently apparently.
  - Corner L-4: Original monument and accessories not found.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner L-3: Re-established 7/12/77 on line between section corners east and west.
  - Corner 10: Established 6/10/77 on line between corners north and south.
  - Corner 1: Established 7/12/77 on line between corners east and west.
  - Corner L-4: Re-established 6/8/77 on line between corners north and south.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |  |   |
|--|---|
| <p><u>Corner L-3:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>14" Y. Birch S73°W 27.9' ¼S NBT<br/>         10" Maple N21°W 24.1' ¼S NBT<br/>         14" Maple S41°E 4.3' ¼S NBT</p> <p><u>Corner 10:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>16" Sugar N15°E 13.2' 1/16S BT<br/>         10" Sugar N70°W 16.2' 1/16S BT<br/>         9" Sugar S60°W 4.4' 1/16S BT</p> | <p><u>Corner 1:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>5" Maple S14°E 13.4' 1/16S BT<br/>         9" Maple S68°W 24.1' 1/16S BT<br/>         16" Maple N24°W 17.9' 1/16S BT</p> <p><u>Corner L-4:</u> Set 1" I.D. x 36" iron pipe with 4" alum. cap.</p> <p>8" Sugar S38°W 3.9' ¼S NBT<br/>         7" Sugar S78°E 14.7' ¼S NBT<br/>         8" Y. Birch N21°E 18.4' ¼S NBT</p> |
|--|---|

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006 (SEAL)