

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>51</u> N. X., R. <u>37</u> X. W.	<u>G8, M11</u>
2. PROPERTY CONTROLLING IN SECTION <u>21</u>	T. <u>51</u> N. X., R. <u>37</u> X. W.	<u>14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 14, 1976, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G8: Original monument and accessories not found. Found 1" I.D. iron pipe 3 feet above ground.

Corner M11: Found 1½" I.D. iron pipe 1½ feet above ground. Set from two original bearing trees: Hemlock 14 S66°W 40 lks. (Badly decomposed)  
Cedar 12 N32°W 41 lks. (Down but in good condition)

Corner 14: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 14: Established on line between ¼ corner north and section corner south.

Corner G8: Re-established corner at iron pipe. Fits good with other corners in area.

Corner M11: Re-established from bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>Corner G8</u>: 1" I.D. iron pipe 3 ft. above ground.</p> <p>9" Elm N47°E 5.4 ft. ½S, NBT 5" Sugar S69°W 14.9 ft. ½S, NBT 5" Sugar N19°W 14.1 ft. ½S, NBT</p> <p><u>Corner M11</u>: 1½" I.D. iron pipe 1½ ft. above ground.</p> <p>5" Cedar S20°E 5.1 ft. S31, NBT 8" Cedar N03°E 24.1 ft. S30, NBT 9" Cedar N77°W 12.8 ft. S25, NBT</p>	<p><u>Corner 14</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>6" Sugar S14°W, 22.1 ft., 1/16S,BT 5" Maple N03°E 21.0 ft., 1/16S,BT 6" Balsam S83°E 3.5 ft., 1/16S,BT 3" Squared Sugar S50°W 2.8 ft.</p>
---	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY DATE August 5, 1976  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

