

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> ^{N.} S. , R. <u>37</u> ^{W.} E.	<u>K12, E12, K11</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E., W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E., W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K12: Original monument and accessories not found. Found 2" I.D. iron pipe 6" above ground.
- Corner E12: Original monument and accessories not found. Found 1½" I.D. iron pipe 28" above ground in fence line at corner of fences north - south - east.
- Corner K11: Original monument and accessories not found. Found old north-south fence.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K12: Re-established 7-2-76 at pipe location. This pipe was witnessed by M.S.H.D.
- Corner E12: Re-established 7-22-76 at pipe location.
- Corner K11: Re-established 7-22-76 by double proportion measurement. Falls in north-south fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| <p><u>Corner K12</u>: 2" I.D. iron pipe 6" above ground.</p> <p>9" Maple N51°W 24.2 ft. ¼S, NBT</p> <p>5" Maple S71°E 10.9 ft. ¼S, NBT</p> <p>5" Maple N30°E 32.7 ft. ¼S, NBT</p> | <p><u>Corner K11</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>9" Y.Birch S51°W 6.5 ft. S35, NBT</p> <p>6" Maple S52°E 5.4 ft. S36, NBT</p> <p>7" Ash N55°W 9.3 ft. S26, NBT</p> |
| <p><u>Corner E12</u>: 1½" I.D. iron pipe 28" above ground.</p> <p>7" Sugar N37°W 12.0 ft. ¼S, NBT</p> <p>5" Sugar S55°W 24.0 ft. ¼S, NBT</p> | |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 6, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

