

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. <u>36</u> , R. <u>37</u> W.	<u>E-9, E-11, C-13</u>
2. PROPERTY CONTROL INC. IN SECTION _____	T. _____ N. _____ S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ W.	_____
LOT NO. _____, RECORDED PLAT _____		
PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER \_\_\_\_\_

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_ established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3 and 4 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a Court of law:

- a. Description of original monument and accessories and/or subsequent restoration:
- Corner E9: Original monument and accessories not found.
  - Corner E11: Original monument and accessories not found. Found 2" O.D. iron pipe.
  - Corner C13: Original monument and accessories not found. Found 1" steel pin.
- b. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner E9: This corner was re-established 5-19-76 by proportion between land calls.
  - Corner E11: Re-established 5-19-76 at 2" O.D. iron pipe. This pipe fits with s north and 1/4 corner west. Has been used as corner for many years.
  - Corner C13: Re-established 6-24-76 at 1" steel pin. Dated prior to 1940.

c. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

<u>Corner E9:</u> 1" I.D. x 36" iron pipe with 4" diam. cap.	<u>Corner C13:</u> 1" Steel pin with cap on top.
N 6° E 27.5 ft. S21, NBT	5" Sugar N25° W 14.5 ft. S31, NBT
S57° E 46.3 ft. S28, NBT	7" Y. Birch N60° E 12.7 ft. S32, NBT
S63° W 54.3 ft. S29, NBT	8" Sugar S16° W 13.1 ft. S 3, NBT

  

<u>Corner E11:</u> 2" O.D. iron pipe.	
S50° E 7.6 ft. S33, NBT	
N27° W 14.3 ft. S29, NBT	
S31° W 13.3 ft. S32, NBT	

DATE \_\_\_\_\_

STATE OF MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES: \_\_\_\_\_

DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY  
Keith L. Sackett  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett

(SEAL)

