

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 51 N. 37 E.	E3, F3
2. PROPERTY CONTROLLING IN SECTION 9	T. 51 N. 37 E.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 26, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 15: Not set on original survey nor subsequently apparently.
- Corner E3: Original monument and accessories not found. Found 1" O.D. x 48" iron pipe set by Copper Range.
- Corner F3: Original monument and accessories not found. Found old location poster as approximate corner 59.9 ft. north.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 15: Established on line between section corner west and 1/4 corner east.
- Corner E3: Re-established at Copper Range pipe. This pipe used as corner for many years and fits good with other corners in area.
- Corner F3: Re-established on line between section corners. Fits good with stream east.

Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- Corner 15: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
7" Sugar N11 E 9.5 ft. 1/16S, BT
7" Sugar S57 E 9.9 ft. 1/16S, BT
- Corner E3: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
9" Sugar N05 W 20.5 ft. S5, NBT
10" Sugar S49 W 28.4 ft. S8, NBT
12" Sugar S49 E 13.9 ft. S9, NBT
- Corner F3: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
6" Sugar N75 W 25.0 ft. 1/4S, NBT
5" Sugar S23 E 14.4 ft. 1/4S, NBT


FILED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

LOCAL AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE June 28, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006