

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 51 N. S., R. 37 W.	F5, E5
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith S. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 23, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3 & 4 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner F5: Original monument and accessories not found.
- Corner E5: Original monument and accessories not found. Found 1" O.D. by unknown length iron set by Copper Range.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner F5: Corner re-established on line between section corners.
- Corner E5: Accepted 1" O.D. iron pipe by Copper Range as corner. This corner fits other corners in area and land calls to stream north.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner F5: Set 1" I.D. x 36" iron pipe with 4" brass cap.
 8" Y. Birch S14°E 26.2 ft. 1/4S, NBT
 10" Basswood N62°W 15.7 ft. 1/4S, NBT
 Squared marker tree 4" Sugar S74°E 2.7 ft. marked 1/4, 9, 16
- Corner E5: 1" O.D. by unknown length iron pipe
 8" Y. Birch S03°E 14.7 ft. S16, NBT
 6" Y. Birch N17°W 15.4 ft. S8, NBT
 8" Sugar N76°E 30.6 ft. S9, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

(SEAL)



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith S. Sackett DATE June 28, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith S. Sackett (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006