

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. S., R. <u>37</u> E. W.	F4
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>51</u> N. S., R. <u>37</u> E. W.	12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 23, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corners F4, 10, 11 and 12: Not set on original survey nor subsequently apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corners F4, 10, 11 and 12: Established on subdivision of section.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner F4: Set 1" I.D.x36" iron pipe with 4" aluminum cap.  
7" Sugar N11°E 16.7 ft. ¼S, BT  
7" Sugar S06°E 8.4 ft. ¼S, BT  
Squared marker tree 5" Sugar N42°W 2.1 ft. marked ¼

Corner 10: Set 1" I.D.x36" iron pipe with 4" aluminum cap.  
8" Y. Birch S65°E 23.5 ft. 1/16 S, BT  
3" Sugar N30°W 10.4 ft. 1/16 S, BT  
Squared marker tree 3" Sugar S35°W 1.4' marked 1/16

Corner 11: Set 1" I.D.x36" iron pipe with 4" aluminum cap.  
6" Sugar N05°W 8.1 ft. 1/16 S, BT  
10" Y. Birch S21°W 29.0 ft. 1/16 S, BT  
Squared marker tree 7" Maple N77°E 4.2' marked 1/16

Corner 12: Set 1" I.D.x36" iron pipe with 4" aluminum cap.  
14" Y. Birch N38°E 10.9 ft. 1/16 S, BT  
8" Sugar S61°E 22.1 ft. 1/16 S, BT  
Squared marker tree 4" Sugar N65°E 3.3 ft. marked 1/16

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE April 23 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

