

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 51N <sup>N.</sup> S <sub>4</sub> , R. 37 <sup>W.</sup>	G4, G3, K3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 26, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner G4: Original monument and accessories not found. Found 1" I.D. by unknown length used as corner.
- Corner G3: Original monument and accessories not found. Found 1" I.D. by unknown length iron pipe 3 ft. out of ground.
- Corner K3: Original monument and accessories not found. Found 1" I.D. by unknown length iron pipe set by Copper Range from original B.T. This corner was also witnessed by Highway Department.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner G4: Accepted iron pipe for corner. Has been used for many years and fits good with other corners in area.
- Corner G3: Accepted iron pipe for corner. Has been used as corner for years.
- Corner K3: Accepted iron pipe for corner as it was set from an original B.T.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                                                                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                         |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <p><u>Corner G4:</u> 1" I.D. by unknown length iron pipe</p> <ul style="list-style-type: none"> <li>7" Sugar S71°W 15.5 ft. ¼S, NBT</li> <li>5" Sugar N37°W 13.1 ft. ¼S, NBT</li> <li>Old Forest Service location poster on</li> <li>5" Sugar N37°E 9.7 ft.</li> </ul> | <p><u>Corner K3:</u> 1" I.D. by unknown length iron pipe 3 feet out of ground.</p> <ul style="list-style-type: none"> <li>7" Sugar N42°E 29.6 ft. S1, NBT</li> <li>9" Sugar S44°E 32.1 ft. S12, NBT</li> <li>17" Sugar N79°W 1.7 ft. S2, NBT</li> </ul> |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
- 
- Corner G3: 1" I.D. by unknown length iron pipe 3 ft. out of ground.
- 14" Sugar N36°W 31.3 ft. S4, NBT
  - 10" Sugar S60°E 13.8 ft. S10, NBT
  - 12" Sugar N35°E 24.3 ft. S3, NBT


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith Louis Sackett DATE June 28, 1976  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith Louis Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006