

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. S., R. <u>37</u> E. W.	<u>11, G5, G6, G7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 11, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 11: Original monument and accessories not found. Found 1" I.D. iron pipe 3 ft. above ground.
- Corner G5: Original monument and accessories not found. Found 1" I.D. iron pipe 1 ft. above ground.
- Corner G6: Original monument and accessories not found. Found 1" I.D. iron pipe flush with ground.
- Corner G7: Original monument and accessories not found. Found 1" I.D. iron pipe 1½ ft. above ground.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 11: Re-established 5-11-76 at pipe location where W. Waara found original bearing tree May 5, 1944.
- Corner G5: Re-established 5-11-76 at pipe location. This pipe was witnessed by M.S.H.D. and has been used for many years.
- Corner G6: Re-established 5-11-76 at pipe location. This pipe has been used for many years.
- Corner G7: Re-established 5-11-76 at pipe location. This pipe has been used for many years. It was also witnessed by M.S.H.D.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| <p><u>Corner 11:</u> 1" I.D. iron pipe 3 ft. above ground.</p> <p>10" Sugar N59°W 21.9 ft. S34, NBT</p> <p>1" Sugar N75°E 26.4 ft. S35, NBT</p> | <p><u>Corner G6:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>9" Sugar N67°W 11.6 ft. ¼S, NBT</p> <p>4" Sugar S10°W 39.0 ft. ¼S, NBT</p> |
| <p><u>Corner G5:</u> 1" I.D. iron pipe 1 ft. above ground.</p> <p>16" Basswood N82°E 25.6 ft. S10, NBT</p> <p>1" Sugar N41°W 19.3 ft. S 9, NBT</p> <p>10" Sugar S59°W 6.5 ft. S16, NBT</p> | <p><u>Corner G7:</u> 1" I.D. iron pipe 1½ ft. above ground.</p> <p>28" W. Pine N60°W 19.7 ft. S16, NBT</p> <p>7" Sugar S29°W 22.8 ft. S21, NBT</p> <p>5" Maple N56°E 37.8 ft. S15, NBT</p> |


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006