

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. <u>8.</u> R. <u>37</u> E. <u>W.</u>	<u>E7, E6, E7, H7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner E7: Original monument and accessories not found. Found 1" I.D. iron pipe 12" above ground.
- Corner E6: Found original bearing tree (Hemlock 30 West 6 lks.) down and rotted. Found 3/4" I.D. iron pipe 1 ft. above ground.
- Corner E7: Original monument and accessories not found. Found 1" I.D. iron pipe 2 ft. above ground.
- Corner H7: Orig. monument and accessories not found. Found 1" I.D. iron pipe 18" above ground.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner E7: Re-established 5-12-76 at pipe. Fits good with other corners in area.
- Corner E6: Re-established 5-12-76 at pipe from original bearing tree.
- Corner E7: Re-established 5-12-76 at pipe. Pipe fits good with other corners in area and land calls. Copper Range has been using it as corner since May 15, 1937.
- Corner H7: Re-established 5-24-76 at pipe. This pipe has been used as corner for many years. It does not fit good with land calls.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| <p><u>Corner E7:</u> 1" I.D. iron pipe 12" above ground.<br/>                 10" oak N12°E 12.3 ft. 1/4S, NBT<br/>                 10" sugar S18°W 28.2 ft. 1/4S, NBT<br/>                 Forest Service location poster on<br/>                 8" sugar S33°W 3.2 ft.</p>    | <p><u>Corner E7:</u> 1" I.D. iron pipe 2 ft. above ground.<br/>                 7" sugar N61°E 10.2 ft. S16, NBT<br/>                 3" Y.birch S33°E 19.3 ft. S21, NBT<br/>                 9" sugar N 61°W 16.0 ft. S17, NBT</p>  |
| <p><u>Corner E6:</u> 3/4" I.D. iron pipe 12" above ground.<br/>                 10" oak S73°W 13.6 ft. 1/4S, NBT<br/>                 10" sugar S83°E 19.7 ft. 1/4S, NBT<br/>                 Copper Range location poster on<br/>                 8" ironwood S35°E 9.8 ft.</p> | <p><u>Corner H7:</u> 1" I.D. iron pipe 18" above ground.<br/>                 4" maple N16°W 11.9 ft. 1/4S, NBT<br/>                 6" spruce S 6°W 30.8 ft. 1/4S, NBT<br/>                 Forest Service location poster on<br/>                 8" balsam N13°E 18.3 ft.</p> |


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett DATE June 28, 1976



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006