

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 51 N. S., R. 37 E. W.	A9, A10
2. PROPERTY CONTROLLING IN SECTION _____ 30	T. 51 N. S., R. 37 E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	

4. PLAT NO. \_\_\_\_\_, RECORDED PLAT \_\_\_\_\_

5. PRIVATE CLAIMS \_\_\_\_\_

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner A9: Original monument and accessories not found. Found 1" I.D. iron pipe 1 foot above ground.
- Corner A10: Original monument and accessories not found. Found 1" I.D. iron pipe. Found old hemlock log with scribing. Possible original bearing tree.
- Corner 3: Not set on original survey nor subsequently apparently. Found 1" I.D. iron pipe 1 foot above ground.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner A9: Re-established 6-21-76 at pipe which fits good with other corners in area and has been used as corner for many years.
- Corner A10: Re-established 6-21-76 at pipe. Fits good with other corners in area.
- Corner 3: Established 6-21-76 at pipe. Fits good with other corners in area.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

- |   |  |
|---|--|
| <p><u>Corner A9:</u> 1" I.D. iron pipe 1 foot above ground.</p> <p>6" Sugar S10°W 6.2 ft. S25, NBT</p> <p>8" Sugar N85°E 18.3 ft. S19, NBT</p> <p>8" Sugar N42°W 8.8 ft. S24, NBT</p> | <p><u>Corner 3:</u> 1" I.D. iron pipe 1 ft. above ground.</p> <p>6" Maple N23°E 7.4 ft. 1/16S, BT</p> <p>8" Sugar S55°W 7.0 ft. 1/16S, BT</p> <p>8" Maple S58°E 14.2 ft. 1/16S, BT</p> |
|---|--|
- Corner A10: 1" I.D. iron pipe.
- 12" Y. Birch N10°W 28.3 ft. 1/4S, NBT
- 22" Sugar S22°W 13.0 ft. 1/4S, NBT
- 12" Sugar S25°E 21.8 ft. 1/4S, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

