

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. S., R. <u>37</u> E. W.	<u>K5, L5, K6</u>
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>51</u> N. S., R. <u>37</u> E. W.	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K5: Original monument and accessories not found. Found 1 1/4" I.D. iron pipe 2 feet above ground.
- Corner L5: Original monument and accessories not found.
- Corner K6: Original monument and accessories not found. Found 1" I.D. iron pipe 4 feet above ground.
- Corner 1: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K5: Re-established 6-23-76 at pipe. Has been used as corner for many years and fits good with land calls.
- Corner L5: Re-established 6-23-76 on line between section corners.
- Corner K6: Re-established 6-23-76 at pipe which has been used as corner for many years.
- Corner 1: Established 6-23-76 on line between section corner west and 1/4 corner east.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <p><u>Corner K5</u>: 1 1/4" I.D. iron pipe 2 ft. above ground.</p> <p>16" Maple N17°E 11.6 ft. S12, NBT</p> <p>8" Spruce N31°W 9.1 ft. S11, NBT</p> <p>8" Spruce S51°E 17.1 ft. S13, NBT</p> | <p><u>Corner K6</u>: 1" I.D. iron pipe 4 ft. above ground.</p> <p>4" Hemlock S58°E 12.4 ft. 1/4S, NBT</p> <p>16" Maple S43°W 26.6 ft. 1/4S, NBT</p> <p>8" Maple N20°W 18.0 ft. 1/4S, NBT</p> |
| <p><u>Corner L5</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>10" Hemlock N53°W 6.1 ft. 1/4S, NBT</p> <p>10" Spruce N50°E 16.0 ft. 1/4S, NBT</p> <p>8" Hemlock S30°E 10.2 ft. 1/4S, NBT</p> | <p><u>Corner 1</u>: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.</p> <p>8" Maple N4°E 16.1 ft. 1/16S, BT</p> <p>12" Maple S52°E 38.2 ft. 1/16S, BT</p> <p>14" Hemlock S55°W 20.1 ft. 1/16S, BT</p> |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE KEITH L. SACKETT, 1906
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

