

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>51</u> N. <u>X.</u> , R. <u>37</u> X. <u>W.</u>		
2. PROPERTY CONTROLLING IN SECTION <u>12</u> T. <u>51</u> N. <u>X.</u> , R. <u>37</u> X. <u>W.</u>	<i>Ortonagon Co.</i>	<u>3, 17, 18</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____, R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

W bdr of 12
betw N 1/16 & 1/4 cor
S 1/16

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 3: Original monument and accessories not found.
- Corner 17: Not set on original survey nor subsequently apparently.
SW Cor. of NW $\frac{1}{4}$ of NW $\frac{1}{4}$ of SW $\frac{1}{4}$.
- Corner 18: Not set on original survey nor subsequently apparently.
NW Cor. of SW $\frac{1}{4}$ of SW $\frac{1}{4}$ of NW $\frac{1}{4}$.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 3: Established 6/13/77 on line between corners north and south.
- Corner 17: Established 6/10/77 on line between corners north and south.
- Corner 18: Established 6/13/77 on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <u>Corner 3:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap. | <u>Corner 18:</u> Set 1" I.D. x 36" iron pipe with 4" aluminum cap. |
|--|---|
- | | |
|---|--------------------------------------|
| 24" Sugar S21 ^o E 18.7' 1/16S BT | 20" Sugar N 6 ^o W 6.7' BT |
| 12" Sugar N11 ^o E 6.1' 1/16S BT | 6" Sugar N84 ^o E 18.5' BT |
| 8" Sugar S72 ^o W 8.7' 1/16S BT | 6" Sugar S15 ^o W 7.0' BT |

Corner 17: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

- 6" Balsam N85^oE 21.3' BT
- 8" Sugar N62^oW 17.6' BT
- 7" Sugar S57^oW 10.4 BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE August 3, 1977
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

