

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON

County	Located In:	Corner Code #
1. Public Land Survey	T 51N R 37W	119
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on July 07, 1992, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(119) Section corner common to Sections 19 & 30, T51N-R36W and Sections 24 & 25 T51N-R37W. Corner Established by U. S. Deputy Surveyor Austin Burt, 1845. Original bearing trees: Maple 12 S68W 25, Hazelock 12 N47W 37. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(119) Original post and accessories not recovered. Found no monumentation at corner position. Original notes show stream calls east and south but these streams have been obliterated by beaver dams. Determined corner to be lost and reestablished the corner by single proportionate measure to the original record between perpetuated original corners 5289.04' north and south. Original line call east, 63.3 ch. to leave swamp as well defined and checks from the monumented corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(119) Placed a 1" x 3/8" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Blazed and scribed the following new bearing trees:
10" Sugar N66E 21.5' (S19 NBT)
10" Sugar S47E 25.5' (S30 NBT)
7" Sugar S34W 6.9' (S25 NBT)
9" Sugar N66W 3.6" (S24 NBT)
Placed 6" squared cedar post N25W 1'.



Signed by Stephan J. Szyszkoski Date 7-14-92
Surveyor's Michigan License No. 33986