LAND CORNER RECORDATION CERTIFICATE Filing Regularement of Act 74, Mich. P.A. 1970

For corners in ONTOWASON		Located In:	Corner Code ≠
_	(County)		
1.	Public Land Survey	T	MB M10
		T R T R	· · · · · · · · · · · · · · · · · · ·
2.	Property Controlling	S 24 T 51N R 37N	1
	in Section	S T R	
3.	Miscellaneous	S T A	

Register of Deeds Stamp & File Number

5. Private Claims ___

Property in Sec.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this cartificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MB) Buarter corner common to Section 19, TSIN-R36N and Section 24, TSIN-R37N. Corner established by U.S. Deputy Surveyor Austin Burt, 1845. Original bearing trees: Maple 10 533N 51, Heslock 8 M42N 46. Found no subsequent record.

(M10) Quarter corner common to Section 30, T51N-R36N and Section 25, T51N-R37N. Corner established by U.S. Deputy Surveyor Austin Durt, 1845. Original bearing trees: Hemlock 18 S9N 18, Hemlock 10 N28N 16. Found no subsequent record.

(7) North 1/15 corner between Section 19, TS1N-R36M and Section 24, TS1N-R37M. Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MB) Original post and accessories not recovered. Found no monumentation or evidence of use at corner position. Determined corner to be lost and reestablished the corner by single proportionate measure to the original record between adjacent corners 2644.52° north and south.

(MIO) Driginal post and accessories not recovered. Found no sonumentation at this position. Determined corner to be lost and reestablished the corner by single proportionate measure to the original record between adjacent corners 2644.52° north and south. Reemants of an old electric fence and an old blue paint line seander north and south, approximately 6° west of the corner.

(7) Established corner midway and on a straight line between recorded corners M7 and M8. Found no monumentation or evidence of use at this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(M6) Placed a 1"x56" iron pipe capped (M10) Placed a 1"x with a 4° dia. cast aluminum MDMR with a 4" dia. cast aluminum MDNR with a 4° dia, cast aluminum MINR tablet. Blazed and scribed the tablet. Blazed and scribed the tablet. Blazed and scribed the following bearing trees: following new bearing trees: following new bearing trees: 8" Sugar N23E 16.7" (1/16S BT) 7" Hemlock SOSE 14.0" (1/45 MBT) B* Healock \$440 18.1' (1/45 NBT) 12° Sugar N55W 11.5' (1/16S BT) 8" Healock 573# 32.1' (1/45 NBT) 12" Heeleck \$40E 11.2" (1/45 NBT) 9" Hemlock S50E 27.0' (1/16S BT) 4" Hemlock N30W 15.5" (1/45 NBT) 5" Healack MBSN 5.5" (1/45 MBT) 7" Hemlock MBIE 6.7" (1/45 MBT) 8" Sugar \$36W 54.1' (1/16S BT) 7" Hemlock M26E 20.0' (1/45 NBT) Corner lies 3' NW of the NW edge of a Placed a 4" squared cedar post, North 1" - Placed a 4" squared maple post North 1" gravel road which bears ME-SM-

Bigned by Stephan J. Syngsfoods

7-14-92

PANE APPROVED BY 1

STEPHAN J SZYSZKOSKI SURVEYOHEM AND SEE NO. 33986