

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
DNTONAGON

County	Located in:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>51N</u> R <u>37W</u>	<u>14</u>
	S <u>25</u> T <u>51N</u> R <u>37W</u>	<u>14</u>
3. Miscellaneous Property in Sec.	S <u>25</u> T <u>51N</u> R <u>37W</u>	<u>7</u>
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on July 07, 1992, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	15	14	13	12	11	10	9	8	7	6	5	4
7													
8	18	17	16	15	14	13	12	11	10	9	8	7	6
9													
10	20	19	18	17	16	15	14	13	12	11	10	9	8
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:

- S.24 (14) South 1/16 corner between Section 19, T51N-R36W and Section 24 T51N-R37W. Corner not established in original survey. Found no subsequent record.
 S.25 (14) South 1/16 corner between Section 30, T51N-R36W and Section 25, T51N-R37W. Corner not established in original survey. Found no subsequent record.
 (7) North 1/16 corner between Section 30, T51N-R36W and Section 25, T51N-R37W. Corner not established in original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- S.24 (14) Established corner midway and on a straight line between recorded corners M8 and M9. Found no monumentation or evidence of use at this position.
 S.25 (14) Established corner midway and on a straight line between recorded corners M10 and M11. Found a 1.5" diameter iron pipe 4.1' West of the corner.
 (7) Established corner midway and on a straight line between recorded corners M9 and M10. Found no monumentation or evidence of use at this position.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

- | | | |
|--|---|--|
| S.24 (14) Placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum NDNR tablet. Blazed and scribed the following bearing trees:
8" Hemlock S64E 33.8' (1/16S BT)
9" Sugar S72W 4.5' (1/16S BT)
10" Sugar N31W 12.6' (1/16S BT)
4" Hemlock N61E 16.3' (1/16S BT)
Placed a 6" squared cedar post N45W 1' | S.25 (14) Placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum NDNR tablet. Blazed and scribed the following bearing trees:
11" Y. Birch N23E 4.8' (1/16S BT)
16" Y. Birch S30E 14.2' (1/16S BT)
23" Hemlock S52W 22.2' (1/16S BT)
24" Hemlock N20W 11.2' (1/16S BT)
Squared and scribed a 4" Hemlock S32E 2.1' | (7) Placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum NDNR tablet. Blazed and scribed the following bearing trees:
7" Sugar N38E 11.8' (1/16S BT)
9" Sugar S87E 30.4' (1/16S BT)
6" Sugar S17E 6.8' (1/16S BT)
12" Y. Birch S81W 7.4' measured on slope (1/16S BT). Placed a 4" squared apple post South 1'. |
|--|---|--|

Signed by Stephan J. Szyszkoski Date 7-11-92
 Surveyor's Michigan License No. 33986

