

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(ONTONAGON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 51 N. R. 37 W.	I-11
2. PROPERTY CONTROLLING IN SECTION	26, T. 51 N. R. 37 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 9, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I-11: Original monument and accessories not found. Found 3/4" I.D. iron pipe 4" out of ground.

Corner 15: Not set on original survey. Found 1-1/4" I.D. iron pipe 15" out of ground.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-11: Restored at 3/4" I.D. iron pipe. Has been used as corner for many years.

Corner 15: Established at iron pipe. Corner fits good with other corners in area. Old fence lines north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-11: 3/4" I.D. by unknown length iron pipe 4" out of ground.

4" Maple S61W 37.0 ft., S34, NBT

9" Balsam N42E 28.1 ft., S26, NBT

8" Balsam S61E 31.5 ft., S35, NBT

Corner 15: 1-1/4" I.D. iron pipe 15" above ground level.

6" Sugar N40E 12.6 ft., 1/16S, BT

8" Sugar S77E 19.4 ft., 1/16S, BT

4" Sugar N82W 17.4 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

