

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	(ONTONAGON COUNTY) LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 51 N. R. 37 E.	E-10
2. PROPERTY CONTROLLING IN SECTION - 29	T. 51 N. R. 37 E.	9
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 8, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E-10: Original monument and accessories not found.

Corner 9: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E-10: Restored corner at spot recorded in 1900. We set corner from notes of subdivision of section (2,652 ft. N87-30-30E from center 1/4 corner).

Corner 9: Established during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E-10: Set 1" I.D. x 36" iron pipe.
 10" Cedar N48E 24.2 ft., 1/4S, NBT
 14" Cedar N69W 33.8 ft., 1/4S, NBT
 4" Sugar S33E 10.7 ft., 1/4S, NBT

Corner 9: Set 1" I.D. x 32" iron pipe on clay bank one (1) chain east of river.
 8" Cedar N75W 16.5 ft., 1/16S, BT
 10" Cedar S55W 7.4 ft., 1/16S, BT
 12" Cedar S11E 7.0 ft., 1/16S, BT

Bank and trees are all sliding into river.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-18-80
CHIEF OF SURVEY PART
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

