

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --	(ONTONAGON COUNTY) LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 51 N. R. 37 E.	D-10
2. PROPERTY CONTROLLING IN SECTION _____	29 T. 51 N. R. 37 E.	8
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 6, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D-10: Found 1" I.D. x unknown length iron pipe set on section subdivision around 1900. M. C. Larsen has notes of survey.

Corner 8: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D-10: Reestablished at iron pipe.

Corner 8: Established midway on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D-10: 1" I.D. x unknown length iron pipe.
 5" Sugar N51E 14.4 ft., 1/4S, BT
 9" Sugar S60W 11.4 ft., 1/4S, BT
 3" Sugar N80W 10.1 ft., 1/4S, BT

Corner 8: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 9" Basswood S25W 28.9 ft., 1/16S, BT
 5" Maple N48W 7.5 ft., 1/16S, BT
 7" Basswood N65E 21.2 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

