

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

ONTONAGON CO.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>51N</u> N. S., R. <u>37W</u> E. W.	<u>H3, F6</u>
2. PROPERTY CONTROLLING IN SECTION_____	.T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	.T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 30, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules, therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner H3: Original monument and accessories not found. Found old east-west blazed line.

Corner F6: Found 1/2" iron pipe in field near old camp. Found Copper Range Location Poster.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H3: Restored on line and midway between corners.

Corner F6: Restored at iron pipe. Fits good for center of section pipe has been used as corner for many years.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H3: Set 1" I.D. by 36" iron pipe with 4" aluminum cap.

12" Sugar	N40°E	3.1 Ft.	1/4 S, NBT
9" Sugar	S84°W	18.5 Ft.	1/4 S, NBT
7" Sugar	S24°E	15.6 Ft.	1/4 S, NBT
8" Sugar	Blazed	4 Sides	S45°W 2.0 Ft.

Corner F6: 1/2" iron pipe x unknown length.

16" Maple	S30°E	39.4 Ft.	1/4 S, BT
10" Maple	N43°W	59.8 Ft.	1/4 S, BT
20" Maple	N78°E	42.2 Ft.	1/4 S, BT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6/80

CHIEF OF SURVEY PARTY
 Keith L. Sackett
 MICHIGAN REGISTERED LAND SURVEYOR
 Michigan Dept. of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006