

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

*ONTONAGON Co.*

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>51N</u> N. S., R. <u>37W</u> E. W.	<u>C12</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>51N</u> N. S., R. <u>37W</u> E. W.	<u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 16, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner C12: Original monument and accessories not found. Found alignment of Highway R.O.W. monument to be 20 ft. east of corner.

Corner 15: Not set on original survey nor subsequently apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner C12: Restored on line and midway between corners.

Corner 15: Established on line and midway between corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner C12: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

9" Sugar N70°W 2.0 Ft. 1/4 S, NBT  
 4" Maple N28°E 13.1 Ft. 1/4 S, NBT  
 7" Sugar S02°W 20.2 Ft. 1/4 S, NBT

Corner 15: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

8" W. Pine S39°W 35.7 Ft. 1/16 S, BT  
 6" R. Pine S62°E 53.2 Ft. 1/16 S, BT  
 10" W. Pine N11°E 67.5 Ft. 1/16 S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6/80  
CHIEF OF SURVEY PART  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

