

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

ONTONAGON Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>51N</u> N. S., R. <u>37W</u> E. W.	<u>A12, L11</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 29, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner A12: Original monument and accessories not found. Found drill bit set by M. C. Larsen from Cedar BT. Not in original notes.

Corner L11: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner A12: Restored at drill bit and old fence corner.

Corner L11: Restored corner midway and on line between corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A12: Drill bit of unknown length.
 14" Oak N82°E 8.9 Ft. 1/4 S, NBT
 6" Y. Birch N10°W 12.2 Ft. 1/4 S, NBT
 4" Sugar S03°E 12.1 Ft. 1/4 S, NBT

Corner L11: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 10" Sugar S10°W 17.9 Ft. 1/4 S, NBT
 12" Oak N43°W 11.1 Ft. 1/4 S, NBT
 8" Maple N60°E 11.0 Ft. 1/4 S, NBT
 4" Sugar Squared East 4.4 Ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6
CHIEF OF SURVEY PART
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

