

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

ONTONAGON CO.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 51N N. S., R. 37W E. W.	E13
2. PROPERTY CONTROLL- ING IN SECTION _____	T. 51N N. S., R. 37W E. W.	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E13: Original monument and accessories not found. Found 1/2" I.D. iron pipe by unknown length located by Highway Department. Pipe is at old fence corner.

Corner 2: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E13: Restored 5-22-79 at pipe. Fits good with other corners in area.

Corner 2: Established 5-25-79 midway and on line between corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E13: 1/2" I.D. by unknown length iron pipe.
 8" Sugar S27°E 13.5 Ft. S 2, NBT
 7" Sugar S65°W 6.4 Ft. S 2, NBT
 12" Sugar N38°W 20.5 Ft. S 32, NBT

Corner 2: Set 1-1/2" iron pipe.
 5" Maple S42°E 15.9 Ft. 1/16 S, BT
 5" Maple N65°E 16.0 Ft. 1/16 S, BT
 6" Maple S01°W 19.4 Ft. 1/16 S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6/80
CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

