

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 24 T 51N R 37W	12
	S _____ T _____ R _____	(GCDB 640320)
3. Miscellaneous Property in Sec.	S 24 T 51N R 37W	16
	S _____ T _____ R _____	(GCDB 660300)
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/05/14 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 24) Center-South 1/16 corner, Section 24. Not previously monumented.

(16-Sec. 24) East 1/16 corner between Sections 24 and 25. Not previously monumented.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 24) Established the position for the corner midway and on a straight line between Quarter corner 1329.41' south and the Center of Section 24 1329.41' north.

(16-Sec. 24) Established the position for the corner midway and on the Section line between Section corner 1257.23' east and Quarter corner 1257.23' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Hemlock N10°E 25.75' mrkd "1/16S BT"
 16" Y.Birch N56°E 14.3' do
 9" Maple S63°W 10.6' do
 3" Hemlock N70°W 10.9' do
 Set sq'd cedar post adjacent.
 E= 7851726.587 N= 225699.936

(16) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Maple S48°E 17.5' mrkd "1/16S BT"
 10" Cedar S35°W 27.9' do
 5" Hemlock S59°W 13.45' do
 13" Hemlock N02°W 6.35' do
 Set sq'd cedar post adjacent.
 E= 7852099.384 N= 225279.338

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
 Coord. Ref.=NGS PID RL0607: N= 222113.185 m. E= 7850163.394 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/30/2014

For the Michigan Department of Natural Resources, Forest Resources Division