

**LAND CORNER RECORDATION CERTIFICATE**

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Stephan J. Szyszkoski

Field Survey Date: July 11, 2017

For corner(s) in: Ontonagon County

Original Public Land Survey Corner		Corner Code
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
Property Corner		1/16 Corner Code
a. S <u>13</u>	T <u>51N</u> R <u>37W</u>	<u>8 (GCDB 620440)</u>
b. S <u>13</u>	T <u>51N</u> R <u>37W</u>	<u>9 (GCDB 660440)</u>
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13	A	B	C	D	E	F	G	H	I	J	K	L	M	13

**Part A. Corner History**

a.) Center-West 1/16 corner, Section 13. Not previously monumented.



b.) Center-East 1/16 corner, Section 13. Not previously monumented.

**Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner**

a.) Established the position for the corner midway and on a straight line between Quarter corner 1218.43' west and the Center of Section 13 1218.43' east.

b.) Established the position for the corner midway and on a straight line between Quarter corner 1307.55' east and the Center of Section 13 1307.55' west.

**Part C: Field Evidence of Perpetuation or Monumentation of Corner**

a.) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 14" Sugar North 3.35' mrkd "1/16S BT"  
 7" Sugar N70°E 21.4' do  
 9" Sugar S20°E 27.05' do  
 9" Maple S63°W 9.3' do  
 Set sq'd cedar post adjacent.  
 E= 7851371.615 N= 227753.247

b.) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 23" Cedar N04°E 7.85' mrkd "1/16S BT"  
 14" Cedar N60°E 14.4' do  
 8" Cedar S68°E 19.55' do  
 6" Maple N85°W 14.05' do  
 Set sq'd cedar post adjacent.  
 E= 7852139.958 N= 227705.335

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.  
 Coord. Ref.=NGS PID RL0593: N= 221669.506 m. E= 7868965.488 m.

Stephan J. Szyszkoski 07/17/2017